



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

## Department of Administrative Services

D'ARCY DIXON PIGNANELLI  
Executive Director

### Division of Facilities Construction and Management

F. KEITH STEPAN  
Director

## ADDENDUM

Date: 13 April 2006

To: Consultants

From: Bill Bowen, Program Director

Reference: Utah State Hospital  
Slate Canyon Waterline Replacement

DFCM Project #: 00144420

Subject: **Addendum No. 1**

Pages:	Addendum	2 page
	<u>Architectural Addendum</u>	<u>0 pages</u>
	Total Pages	2 pages

---

***Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.***

1.1 Schedule changes: There are no schedule changes per this Addendum.

1.2 Contractor questions:

1.2.1 Could spoils from trench excavation be placed outside the 10 ft. right-of-way?

**No, but they can be spread evenly on the trail.**

1.2.2 Could rock larger than 6" be placed back in the trench as backfill?

**Yes, but it must remain outside of the pipe envelope.**

- 1.2.3 Could large rocks not used as backfill be left on site instead of hauled off?  
Yes, as long as they are not blocking the trail or placed in the drainage.
- 1.2.4 Can trees be removed and/or trimmed back so they don't hang over into the right-of-way?  
At this time, it is anticipated that no trees may be removed. However, limited trimming may be allowed with prior approval of the Forest Service.
- 1.2.5 Could a rock clause be added to the specifications?  
The current geotechnical reports indicate that the sub-surface material to be encountered does not merit this requirement. However, the State may choose to negotiate a "rock clause" with the selected contractor.

*End of Addendum*