



**Olene S. Walker**  
*Governor*  
**S. Camille Anthony**  
*Executive Director*  
**F. Keith Stepan**  
*Director*

# State of Utah

## Division of Facilities Construction & Management

Department of Administrative Services  
4110 State Office Building  
Salt Lake City, Utah 84114  
Phone (801) 538-3018  
Fax (801) 538-3267

## MEMORANDUM

Date: 8 September 2005

To: Bidders

From: Kurt Baxter, Project Manager, DFCM

Reference: **UNG Camp Williams Sewer Extension, 05216480**

Subject: **Addendum No. 1**

---

### ITEM NUMBER 1

#### Drawings – Sheet Number 3 of 5

- Revise Construction Note #3 to read “Four feet of cover will be required over all sewer lines, compacted to 90% max dry density per ASTM D-1557 in 12” lifts.”
- Add Construction Note #4, “repair landscape and sprinkler system. Submit plan for landscape installation and irrigation system to engineer for approval prior to work.”

### ITEM NUMBER 2

#### Drawings – Sheet Number 4 of 5

- Revise Construction Note #3 to read “Four feet of cover will be required over all sewer lines, compacted to 90% max dry density per ASTM D-1557 in 12” lifts.”
- Add Construction Note #4, “repair landscape and sprinkler system. Submit plan for landscape installation and irrigation system to engineer for approval prior to work.”
- Add note on plan view, “Remove & replace concrete curb” where proposed sewer line runs under existing concrete curb.

- Add note on plan view, “Relocate existing trees – coordinate w/ owner (replace w/ 2 new 3” caliper Tilia Cordata “Little Leaf Linden” trees upon completion of sewer line)” pointing to the 2 existing trees next to the proposed sewer line.
- Replace sod in disturbed areas (East of existing building).

### **ITEM NUMBER 3**

#### **Drawings – Sheet Number 5 of 5**

- Add General Note #3, “Compact backfill to 90% max dry density per ASTM D-1557 in 1’ lifts.”

End of Addendum