



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

D'ARCY DIXON PIGNANELLI
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN
Director

MEMORANDUM

Date: 12 July 2005

To: Contractors

From: Rick James, DFCM

Reference: Ogden Weber Applied Technology College
BDO Build-Out Phase III
DFCM Project No. 05183240

Subject: **Addendum No. 2**

Pages	Addendum	2 pages
	Total	2 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in this Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

2.1 Sheet P-201, add the following:

Install water coolers in the small alcove on the north side of Storage 128. Run a 1/2" water line from the cold water line above the new restrooms, and drop down inside the wall behind the water coolers to serve the water coolers. Run a 2" waste line west to connect to the new 4" waste from the restrooms. Rise a 2" vent into the ceiling space and route to the nearby vent lines in the restroom.

2.2 Specifications Section 15400, add the following:

BI-LEVEL ACCESSIBLE WATER COOLER

A. Operating bar on front. 8.0 GPH of 50 deg F water with 90 deg F room temperature, 1/5 horsepower compressor motor, 120 V, 60 Hz, single phase. One piece stainless steel back splash and basin. Flexi-guard or chrome plated brass bubbler. Anchor bottom of fountain to wall. Install 3/8 inch IPS union connection and Chicago No. 376 stop to building supply line. Install 1-1/4 inch IPS slip cast brass "P" trap. Install trap so it is concealed.

B. Approved Manufacturers: Elkay EBFATL-8 approved alternate by Halsey-Taylor, Oasis, or Sunroc.

End of Addendum