

CODE ANALYSIS			
APPLICABLE CODES			
	Year		Year
International Building Code	2003	National Electrical Code	2003
International Mechanical Code	2003	Uniform Code for	
International Plumbing Code	2003	Building Conservation	
International Fire Code	2003	ADA Accessibility	
International Energy		Guidelines	ICC/ANSI 117.1 1998
Conservation Code	2003		

A. Occupancy and Group: UNLIMITED MALL BUILDING

Change in Use: Yes No ☒ Mixed Occupancy: Yes ☒ No
Special Use and Occupancy (e.g. High Rise, Covered Mall): UNLIMITED MALL BUILDING

B. Seismic Design Category: D Design Wind Speed: 90 mph

C. Type of Construction (circle one):

I/A I/B II/A ☒ II/B III/A III/B IV/HT V/A V/B

D. Fire Resistance Rating Requirements for the Exterior Walls based on the fire separation distance (in hours):
North: South: East: West:

E. Mixed Occupancies: Nonseparated Uses:

F. Sprinklers:
Required: ☒ Provided: ☒ Type of Sprinkler System:

G. Number of Stories: 1 Building Height: 18'

H. Actual Area per Floor (square feet): 1800 SF

I. Tabular Area: UNLIMITED MALL BUILDING

J. Area Modifications:

a) $A_a = A_t + \left[\frac{A_t I_t}{100} \right] + \left[\frac{A_t I_s}{100} \right]$ $I_t = 100 \left[\frac{F}{P} - 0.25 \right] \frac{W}{30}$

b) Sum of the Ratio Calculations for Mixed Occupancies:

$\frac{\text{Actual Area}}{\text{Allowable Area}} \leq 1$

c) Total Allowable Area for:

1) One Story:
2) Two Story: $A_a(2)$
3) Three Story: $A_a(3)$

d) Unlimited Area Building: Yes ☒ No Code Section: 401

K. Fire Resistance Rating Requirements for Building Elements (hours).

Fire-Resistive Requirements:	Type: II-B
Bearing walls - Interior:	0
Exterior Non-Bearing Walls:	0
Structural Frame:	0
Partitions:	1
Shafts:	1 Hr.
Floors - Ceilings:	0
Roofs - Ceilings:	0

L. Design Occupant Load: EXIST. BLDG: 471 ADDITION: 120
Exit Width Required: 118" Exit Width Provided: 432"

M. Minimum Number of Required Plumbing Facilities:

a) Water Closets - Required (m) 2.5 (f) 5 Provided (m) 11 (f) 11
b) Lavatories - Required (m) 1.5 (f) 1.5 Provided (m) 6 (f) 6
c) Bath Tubs or Showers:
d) Drinking Fountains: Service Sinks:

FOOTNOTES:

1) In case of conflict with the U.S. Department of Justice Federal Registers Parts I through V - ADA Guidelines and specific reference to the International Building Code Accessibility Chapters, the more restrictive requirement shall govern.

2) Additional Code Information shall be provided at the discretion of the Building Official for Complex Buildings. Including, but not limited to:

a) High Rise Requirements.
b) Atriums.
c) Performance Based Criteria.
d) Means or Egress Analysis.
e) Fire Assembly Locator Sheet.
f) Exterior and Interior Accessibility Route.
g) Fire Stopping, Including Tested Design Number.

PROJECT TEAM

OWNER: DFCM Kurt Baxter Project Manager 4110 State Office Bldg. Salt Lake City, Utah 84114 phone (801) 538-3174	USER: UVSC James L. Michaelis Associate Vice President Facilities Planning 800 West University Parkway Orem, Utah 84058-5999 phone (801)863-8776	ARCHITECT: AXIS ARCHITECTS Pierre O. Langue AIA 610 I Street Salt Lake City, Utah 84103 phone (801)355-3003 fax (801)355-8578
STRUCTURAL: Bsumek Mu Reinardt Bsumek 345 South 400 East Salt Lake City, Utah 84111 phone (801)575-8223 fax (801)532-3778	MECHANICAL: Spectrum Engineers Wade Bennion 175 South Main Street Salt Lake City, Utah 84111 phone (801)328-5151	ELECTRICAL: BNA Consulting Carol Feldman 635 S. State Street Salt Lake City, Utah 84111 phone (801)355-3003 fax (801)355-8578

VINCINITY MAP

A detailed vicinity map of the project location. The map shows a network of streets including 10th Avenue, 11th Avenue, 12th Avenue, 13th Avenue, 14th Avenue, 15th Avenue, 16th Avenue, 17th Avenue, 18th Avenue, 19th Avenue, 20th Avenue, 21st Avenue, 22nd Avenue, 23rd Avenue, 24th Avenue, 25th Avenue, 26th Avenue, 27th Avenue, 28th Avenue, 29th Avenue, 30th Avenue, 31st Avenue, 32nd Avenue, 33rd Avenue, 34th Avenue, 35th Avenue, 36th Avenue, 37th Avenue, 38th Avenue, 39th Avenue, 40th Avenue, 41st Avenue, 42nd Avenue, 43rd Avenue, 44th Avenue, 45th Avenue, 46th Avenue, 47th Avenue, 48th Avenue, 49th Avenue, 50th Avenue, 51st Avenue, 52nd Avenue, 53rd Avenue, 54th Avenue, 55th Avenue, 56th Avenue, 57th Avenue, 58th Avenue, 59th Avenue, 60th Avenue, 61st Avenue, 62nd Avenue, 63rd Avenue, 64th Avenue, 65th Avenue, 66th Avenue, 67th Avenue, 68th Avenue, 69th Avenue, 70th Avenue, 71st Avenue, 72nd Avenue, 73rd Avenue, 74th Avenue, 75th Avenue, 76th Avenue, 77th Avenue, 78th Avenue, 79th Avenue, 80th Avenue, 81st Avenue, 82nd Avenue, 83rd Avenue, 84th Avenue, 85th Avenue, 86th Avenue, 87th Avenue, 88th Avenue, 89th Avenue, 90th Avenue, 91st Avenue, 92nd Avenue, 93rd Avenue, 94th Avenue, 95th Avenue, 96th Avenue, 97th Avenue, 98th Avenue, 99th Avenue, 100th Avenue. The project location is marked with a black circle and a line pointing to the text 'PROJECT LOCATION'. A north arrow is located in the bottom left corner, and a scale bar is located in the bottom right corner.

OVERALL SITE PLAN

1"=100'-0"

LOT L

LOT M

PROJECT LOCATION

BUILDING: PHYSICAL EDUCATION BUILDING
 Occupancy : B-2 Unlimited Area
 Construction: II B - Fire Sprinkled

BUILDING: SPECIAL EVENT CENTER
 Occupancy : A2-1 UNLIMITED AREA
 Construction: I A - Fire Sprinkled

LA























PE

MC



















PS

F

SYMBOL LEGEND

 <p>ROOM NAME</p>	 <p>T.O. ELEV. =</p>	 <p>A1 A100</p> <p>DETAIL REFERENCE</p>	 <p>A1 A100</p> <p>EXTERIOR ELEVATION</p>	 <p>A1 A100</p> <p>BUILDING SECTION</p>	 <p>A1 A100</p> <p>WALL SECTION</p>
 <p>100 A1</p> <p>DOOR SYMBOL</p>	 <p>100 A1</p> <p>DOOR NUMBER HARDWARE GROUP</p>	 <p>100 A1</p> <p>FRAME NUMBER</p>	 <p>100 A1</p> <p>DOOR TYPE</p>	 <p>MATCH LINE</p>	 <p>AREA 1 AREA 2</p>
 <p>B1 F1</p> <p>NORTH WALL FINISH BASE FINISH</p>	 <p>LINE MATCH SYMBOL</p>	 <p>A1 A100</p> <p>INT. ELEVATION SYMBOL</p>	 <p>A1 A100</p> <p>GLAZING TYPE</p>	 <p>100'-0"</p> <p>SPOT ELEVATION MARKER</p>	 <p>1</p> <p>WINDOW NUMBER</p>
 <p>B1 F1</p> <p>FINISH SYMBOL</p>	 <p>ACT 8'-0"</p> <p>CEILING TYPE AND HEIGHT</p>	 <p>A1 A100</p> <p>BUILDING SECTION</p>	 <p>6</p> <p>WALL TYPE</p>		

GRAPHIC SYMBOLS

	EARTH		STEEL		PLYWOOD
	CEMENTIOUS BACKER BD.		RIGID INSULATION		WOOD FINISH
	CMU		ASPHALT PAVING		ALUMINUM
	BRICK		DENSGLASS SHEATHING		BATT INSULATION
	WOOD BLOCKING		GRAVEL		CERAMIC TILE
	WOOD FRAMING		CONCRETE		GYPSUM SHEATHING

DRAWING INDEX

GENERAL

G101	GENERAL INFORMATION
------	---------------------

ARCHITECTURAL

AD101	DEMOLITION FLOOR PLAN
AE101	FIRST FLOOR PLAN
AE102	ROOF PLAN
AE111	REFLECTED CEILING PLAN
AE201	BUILDING ELEVATIONS
AE301	BUILDING SECTIONS
AE302	BUILDING SECTIONS
AE401	WALL SECTIONS

STRUCTURAL

S001	STRUCTURAL GENERAL NOTES
S101	FOOTING & FOUNDATION PLAN
S102	ROOF FRAMING PLAN
S301	STRUCTURAL SECTIONS

MECHANICAL


ME001	MECHANICAL SYMBOLS LEGEND
MD101	MECHANICAL DEMOLITION PLAN
MJ101	MECHANICAL FLOOR PLAN

ELECTRICAL

EG101	ELECT. SYMBOLS SCHEDULES AND NOTES
EE101	ELECTRICAL FLOOR PLAN

NOTE: THE SHEETS LISTED ABOVE REPRESENT A FULL SET OF CONSTRUCTION DOCUMENTS AND INCLUDE A DETAIL BOOK AND A PROJECT MANUAL AND SHALL NOT BE SEPARATED. ANY CONTRACTOR, SUBCONTRACTOR, VENDOR OR ANY OTHER PERSON PARTICIPATING IN OR BIDDING ON THIS PROJECT SHALL BE RESPONSIBLE FOR RECEIVING ALL THE CONSTRUCTION DOCUMENTS INCLUDING BUT NOT LIMITED TO DRAWINGS, DETAILS, PROJECT MANUAL, SPECIFICATIONS AND ANY AND ALL ADDENDA ISSUED.

GI101



Axis Architects

610 " 1 " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

DFCM

DFCM

UVSC HALLWAY
ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision # Date

...

...


...

...

Axis Job # 0510
Owner # DFCM # 05264790
Date 01-15-06
Drawn PL
Checked PL


FLOOR PLAN

AE101




B3 ROOF PLAN

SCALE: 1/4"=1'-0"




A1 ROOF DRAIN DETAIL

SCALE: 1 1/2"=1'-0"




A2 COPING DETAIL

SCALE: 1 1/2"=1'-0"



A3 SCUPPER DETAIL

SCALE: 1 1/2"=1'-0"




A4 FLASHING JOINT DETAIL

SCALE: FULL SCALE

NOTES

1. PROVIDE TAPERED INSULATION TO CREATE SLOPE.
2. MATCH NEW INSULATION ELEVATION WITH EXISTING AT EXISTING SCUPPERS.
3. REPAIR EXISTING ROOFING MEMBRANE 5' PAST PARAPETS TYP.



UVSC HALLWAY
ADDITION - DFCM
PHYSICAL EDUCATION BLDG UVSC CAMPUS


Revision # Date

.....

Axis Job # 0510
Owner # DFCM # 05264790
Date 01-15-06
Drawn PL
Checked PL

ROOF PLAN


AE102






PHYSICAL EDUCATION BLDG UVSC CAMPUS

Axis Job #	0510
Owner #	DFCM # 05264790
Date	01-15-06
Drawn	PL
Checked	PL

111





GLAZING SCHEDULE


- ☐ A EXISTING 1" INSULATED GLASS - BRONZE TINT
- ☐ B EXISTING 1" INSULATED TEMPERED GLASS - BRONZE TINT
- ☐ C NEW 1" INSULATED GLASS - BRONZE TINT
- ☐ D NEW 1" INSULATED TEMPERED GLASS - BRONZE TINT

KEYNOTE LEGEND 1A

ELEVATIONS

- 2 - SITE WORK:
- 2A SLOPE GRADE AWAY FROM BLDG. TYP.
- 3 - CONCRETE:
- 3A NEW CONCRETE FOUNDATION WALL - SEE STRUCT.
- 3B NEW CONCRETE COLUMN - SEE STRUCT.
- 3C NEW CONCRETE BEAM - SEE STRUCT.
- 3D CONTROL JOINT
- 3E FORM JOINT
- 3F 2" EXPANSION JOINT
- 3G CONCRETE FORM TIE
- 3H EXISTING CONC. COLUMN TO REMAIN
- 3J EXISTING CONC. BEAM TO REMAIN
- 3K EXISTING CONC. WALL TO REMAIN
- 3L CUT-OUT IN CONC. BEAM WITH GALV. STEEL SCUPPER
- 3M OPENING IN CONC. BEAM FOR MECHANICAL LOUVER

- 7 - THERMAL AND MOISTURE PROTECTION:
- 7A PRE-FINISHED METAL FLASHING
- 8 - DOORS AND WINDOWS:
- 8A EXISTING WINDOW SYSTEM - RELOCATED
- 8B NEW MULION TO MATCH EXISTING OR CUT EXISTING MULION.
- 9 - FINISHES
- 9A RECESS PAINTED DARK BRONZE - SMOOTH CONC.
DO NOT SANDBLAST
- 15 - MECHANICAL
- 15A LOUVER SEE MECHANICAL



Axis Architects

610 " 1 " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

DFCM

DFCM

UVSC HALLWAY
ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision #	Date
1	01-15-06
2	01-15-06
3	01-15-06
4	01-15-06
5	01-15-06

Axis Job # 0510

Owner # DFCM # 05264790


Date 01-15-06

Drawn

Checked

BUILDING SECTIONS

AE301



Axis Architects

610 " 1 " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

DFCM

UVSC HALLWAY
ADDITION - DFCM



PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision #	Date
...	...
...	...
...	...

Axis Job # 0510
Owner # DFCM # 05264790
Date 01-15-06
Drawn
Checked

BUILDING SECTIONS


AE302



**UVSC HALLWAY
ADDITION - DFCM**
PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision	#	Date

Axis Job #	0510
Owner #	DFCM # 05264790
Date	01-15-06
Drawn	PL
Checked	PL



Axis Architects

610 • 1 • STREET
SALT LAKE CITY
UTAH 84103
P 355-3003
F 355-8578

UVSC HALLWAY
ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS
DESIGN DEVELOPMENT

Revision #	Date

Axis Job # 0510

Owner #


Date 12-14-05

Drawn

Checked

FOOTING PLAN

S101



Axis Architects

610 • 1 • STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

UVSC HALLWAY
ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS


DESIGN DEVELOPMENT

Revision #	Date
1	12-14-05

Axis Job # 0510
Owner #
Date 12-14-05
Drawn
Checked

FOOTING PLAN

S102



Axis Architects

610 "1" STREET
SALT LAKE CITY
UTAH 84103
P 355-3003
F 355-8578

UVSC HALLWAY
ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS

DESIGN DEVELOPMENT

Revision # Date


.....

Axis Job # 0510
Owner #
Date 12-14-05
Drawn
Checked
Bsumek Mu # 25136


STRUCTURAL SECTIONS

S301


File name: P:\2005\20050659\1Drawings\Sheet\59ME001.dwg Last Plotted: 01/18/2006 @ 16:37 By: ewl



3 GOOSENECK DETAIL
SCALE: NOT TO SCALE



2 OVERFLOW DRAIN LINE DETAIL
SCALE: NOT TO SCALE



1 CLEANOUT TO GRADE DETAIL
SCALE: NOT TO SCALE

DIFFUSER AND GRILLE SCHEDULE				
DESIGNATION	MANUF.	MODEL	DESCRIPTION	MAX SP DROP (IN. WC)
L-1	AIRLITE	K6776	WALL LOUVER , STATIONARY 6 INCH THICK 35 BLADE, 12 GA., EXT. ALUMINUM BLADES, 8 GA, EXT. ALUMINUM JAMBS. CHANNEL FRAME. BIRD SCREEN. COLOR AND FINISH TO BE SELECTED BY ARCHITECT.	N/A
LS-1	PRICE	SDS 100	LINEAR SLOT DIFFUSER, CURVED FACE, FRAME 16 FIELD VERIFY EXACT DIMENSIONS. COLOR AND FINISH TO BE SELECTED BY ARCHITECT.	0.1

ABBREVIATIONS			
NOTE: ALL ABBREVIATIONS MAY NOT BE USED			
AD	ACCESS DOOR	MCA	MINIMUM CIRCUIT AMPS
AIR	AIR CONDITION(-ING, -ED)	MFR	MANUFACTURER
COND		MIN	MINIMUM
APD	AIR PRESSURE DROP	N/A	NOT APPLICABLE
BD	BALANCING DAMPER	NC	NORMALLY CLOSED
BHP	BRAKE HORSE POWER	NC	NOISE CRITERIA
BTU	BRITISH THERMAL UNIT	NIC	NOT IN CONTRACT
BTUH	BTU/HOUR	NO	NORMALLY OPEN
CFH	CUBIC FEET PER HOUR	NPSH	NET POSITIVE SUCTION
CFM	CUBIC FEET PER MINUTE		HEAD
CLG	COOLING	NTS	NOT TO SCALE
COMP	COMPONENT	OA	OUTSIDE AIR
COND	CONDENS(-ER, -ING, -ATION)	OD	OUTSIDE DIAMETER
CV	CONTROL VALVE	OZ	OUNCE
CW	COLD WATER	PD	PRESSURE DROP OR DIFFERENCE
DIA	DIAMETER	PG	PROPYLENE GLYCOL
DISCH	DISCHARGE	PH	PHASE
DP	DEPTH OR DEEP	PPM	PARTS PER MILLION
DB	DRY BULB TEMPERATURE	PRESS	PRESSURE
(E)	EXISTING	PSF	POUNDS PER SQUARE FOOT
EER	ENERGY EFFICIENCY RATIO	PSI	POUNDS PER SQUARE INCH
EFF	EFFICIENCY	PSIA	PSI ABSOLUTE
EG	ETHYLENE GLYCOL	PSIG	PSI GAUGE
ELEC	ELECTRIC	R	THERMAL RESISTANCE
ELEV	ELEVATION	RA	RETURN AIR
ENT	ENTERING	RECIRC	RECIRCULATE
EVAP	EVAPORAT(-E, -ING, -ED, -OR)	REFR	REFRIGERATION
EWT	ENTERING WATER TEMPERATURE	REQD	REQUIRED
EXT	EXTERNAL	RLA	RATED --- AMPS
(F)	FUTURE	RPM	REVOLUTIONS PER MINUTE
F	FAHRENHEIT	RW	RAINWATER
FC	FLEXIBLE CONNECT(-OR, -ION)	SA	SUPPLY AIR
FD	FIRE DAMPER	SC	SHADING COEFFICIENT
FLA	FULL LOAD AMPS	SCFM	STANDARD CUBIC FEET PER MINUTE
FPI	FINS PER INCH	SCW	SOFT COLD WATER
FFM	FEET PER MINUTE	SF	SAFETY FACTOR
FPS	FEET PER SECOND	SH	SENSIBLE HEAT
FSD	FIRE SMOKE DAMPER	SL	SEA LEVEL
FT	FEET	SP	STATIC PRESSURE
GAL	GALLON(S)	SPCS(S)	SPECIFICATION(S)
GPH	GALLONS PER HOUR	SQ	SQUARE
GPM	GALLONS PER MINUTE	STD	STANDARD
HD	HEAD	STM	STEAM
HG	MERCURY	TEMP	TEMPERATURE
HR	HOUR	TD	TEMP. DROP OR DIFF.
HT	HEIGHT	THERM	THERMAL
HTG	HEATING	TOT	TOTAL
HP	HORSE POWER	TSTAT	THERMOSTAT
HW	HOT WATER	V	VOLT
HZ	HERTZ(FREQUENCY)	VAC	VACUUM
ID	INSIDE DIAMETER	VAV	VARIABLE AIR VOLUME
IN	INCH	VEL	VELOCITY
KW	KILOWATT	VENT	VENT, VENTILATION
LAT	LEAVING AIR TEMPERATURE	VERT	VERTICAL
LBS	POUNDS	VFD	VARIABLE FREQUENCY DRIVE
LG	LENGTH	VOL	VOLUME
LH	LATENT HEAT	WG	WATER COLUMN
LRA	LOCKED ROTOR AMPS	WG	WATER GAUGE
LVG	LEAVING WATER TEMPERATURE	WPD	WATER PRESSURE DROP
LWT	LEAVING WATER TEMPERATURE	WTR	WATER
MAX	MAXIMUM	WT	WEIGHT
MBH	THOUSAND BTU PER HOUR	WB	WET BULB TEMP
		YR	YEAR

SYMBOL LEGEND		
SYMBOL	DESCRIPTION	
DUCTWORK		
SINGLE LINE	DOUBLE LINE	DESCRIPTION
		RECTANGULAR SUPPLY DUCT UP
		RECTANGULAR SUPPLY DUCT DOWN
		RECTANGULAR RETURN DUCT UP
		RECTANGULAR RETURN DUCT DOWN
		RECTANGULAR EXHAUST DUCT UP
		RECTANGULAR EXHAUST DUCT DOWN
		ROUND DUCT UP
		ROUND DUCT DOWN
		ACCOUSTICALLY LINED RECTANGULAR DUCT
		90° RECTANGULAR ELBOW WITH TURNING VANES
		90° RADIUS ELBOW R=1.5
		DUCT SIZE OR SHAPE TRANSITION
		OPPOSED BLADE BALANDING DAMPER (O.B.D.) IN RECT DUCT
		EXISTING DUCT
		DUCT TO BE REMOVED

SYMBOL LEGEND	
SYMBOL	DESCRIPTION
PLUMBING PIPING	
	SOIL, WASTE - ABOVE GRADE
	SOIL, WASTE - BELOW GRADE
	RAINWATER - ABOVE GRADE
	RAINWATER - BELOW GRADE
	OVERFLOW RAINWATER ABOVE GRADE
	OVERFLOW RAINWATER BELOW GRADE
	STORM DRAIN
	EXISTING PIPE
	EXISTING PIPE TO BE REMOVED

- ### GENERAL MECHANICAL NOTES
- DO NOT ROUTE DUCTS AND PIPES ABOVE ELECTRICAL PANELS. ALL ELECTRICAL PANELS MUST HAVE CLEAR ACCESS SPACE IN FRONT OF PANEL 4'-0" DEEP AND 6'-6" HIGH. DO NOT ROUTE DUCTS AND PIPES IN ELECTRICAL ROOMS, EXCEPT DUCTS AND PIPES SERVING THE ROOM.
 - ALL DUCT DIMENSIONS ARE INSIDE FREE AREA DIMENSIONS. ADJUST SHEET METAL DIMENSION FOR LINED DUCT.
 - IF CONTRACTOR ENCOUNTERS MATERIAL WHICH MAY CONTAIN ASBESTOS IMMEDIATELY STOP WORK IN THIS AREA AND NOTIFY THE OWNER.
 - PROVIDE CEILING ACCESS PANELS AS REQUIRED WHERE MECHANICAL EQUIPMENT, VALVES, VAV BOXES, FIRE DAM- PERS, ETC. ARE LOCATED ABOVE INACCESSIBLE CEILINGS.
 - ALL DUCT AND FLUE PENETRATIONS THRU 1 HOUR ROOF ASSEMBLY TO BE ENCLOSED WITH 2 SHEET ROCK LAYERS FROM SHEET ROCK AT BOTTOM OF ROOF TRUSSES TO ROOF DECK.
 - STEEL ROOF DECK SHALL NOT BE USED TO SUPPORT LOADS FROM PIPING, DUCTWORK OR EQUIPMENT, UNLESS NOTED OTHERWISE. HANGER LOADS LESS THAN 50 LBS. MAY BE HUNG FROM THE STEEL ROOF DECK IN CASES WHEN HANGING FROM THE STEEL ROOF DECK CANNOT BE AVOIDED; THE ATTACHMENT METHOD MUST DISTRIBUTE THE LOAD ACCROSS THE DECK AS APPROVED BY THE STRUCTURAL ENGINEER.

MECHANICAL SHEET INDEX	
SHEET NO	SHEET TITLE
ME001	MECHANICAL SYMBOLS LEGEND AND SHEET INDEX
MD101	MECHANICAL DEMOLITION FLOOR PLAN
MH101	MECHANICAL FLOOR PLAN

SYMBOL LEGEND	
SYMBOL	DESCRIPTION
REFERENCE AND LINE SYMBOLS	
	DETAIL INDICATOR: # INDICATES DETAIL NUMBER, SHEET INDICATES DRAWING SHEET WHERE DETAIL IS SHOWN.
	ELEVATION OR SECTION INDICATOR, EXTERIOR: # INDICATES ELEVATION OR SECTION NUMBER, SHEET INDICATES DRAWING SHEET WHERE ELEVATION OR SECTION IS SHOWN.
	ELEVATION OR SECTION INDICATOR, INTERIOR: # INDICATES ELEVATION OR SECTION NUMBER, SHEET INDICATES DRAWING SHEET WHERE ELEVATION OR SECTION IS SHOWN.
	ROOM OR SPACE NUMBER.
	KEYNOTE INDICATOR.
	REVISION INDICATOR.
	EQUIPMENT INDICATOR.
	PLUMBING FIXTURE INDICATOR.
	DIFFUSER/GRILLE INDICATOR.
	DIFFUSER/GRILLE INDICATOR.
	BREAK, STRAIGHT
	BREAK, ROUND.
	MATCH LINE INDICATOR
	HIDDEN FEATURES LINE: HIDDEN, THIN LINE.
	CONTRACT LIMIT LINE: DASHDOT, WIDE LINE.
	NEW CONNECTION POINT TO EXISTING

UVSC HALLWAY
ADDITION - DFCM
PHYSICAL EDUCATION BLDG UVSC CAMPUS
DESIGN DEVELOPMENT

Revision #	Date
1	11/29/05
2	
3	
4	
5	
Axis Job #	0510
Owner #	
Date	11/29/05
Drawn	JTU
Checked	TNB


MECHANICAL SYMBOLS
LEGEND AND
SHEET INDEX

ME001

Axis Architects

610 " I " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

File name: P:\2005\20050659\1Drawings\Sheet\59MD101.dwg Last Plotted: 01/18/2006 @ 16:38 By: ewl



UVSC HALLWAY
ADDITION - DFCM
PHYSICAL EDUCATION BLDG UVSC CAMPUS
DESIGN DEVELOPMENT

Revision #	Date
1	11/29/05
2	
3	
4	
5	

Axis Job #	0510
Owner #	
Date	11/29/05
Drawn	JTU
Checked	TNB


MECHANICAL
DEMOLITION
FLOOR PLAN

Axis Architects


610 " I " STREET
SALT LAKE CITY
UTAH 84103
P 355-3003
F 355-6578

MD101

File name: P:\2005\20050659\1Drawings\Sheet\59MH101.dwg Last Plotted: 01/18/2006 @ 16:37 By: ewl



1 MECHANICAL FLOOR PLAN
SCALE: 1/4"=1'-0"



SHEET KEYNOTES

- EXTEND OVERFLOW DRAIN LINE TO DAYLIGHT STRAIGHT OUT THE SIDE OF THE SLOPED GRADE EXPOSE 4" OF PIPE FOR VISUAL INSPECTION. SEE DETAIL 2/ME501.
- CONNECT TO EXISTING 10" STORM DRAIN LINE .FIELD VERIFY SIZE, LOCATION, AND ELEVATION.
- CONNECT TO EXISTING 10" SEWER LINE. FIELD VERIFY SIZE, LOCATION, AND ELEVATION.
- CONNECT TO 6" STORM DRAIN LINE HERE USE CAST IRON FOR PIPE MATERIAL BEYOND 5'-0" OF THE BUILDING. FIELD VERIFY SIZE, LOCATION, AND ELEVATION.
- 4" GOOSENECK.

GENERAL SHEET NOTES

- EXTEND FIRE SPRINKLER SYSTEM INTO ADDITION AREAS FROM EXISTING CROSS MAIN. PROVIDE PIPING AND HEADS AS REQUIRED BY NFPA 13. PROVIDE SHOP DRAWINGS AND HYDRAULIC CALCULATIONS. SUBMIT TO ENGINEER AND AUTHORITY HAVING JURISDICTION FOR APPROVAL. DESIGN BASE HYDRAULIC CALCULATIONS ON FLOW AND PRESSURE AT BASE OF EXISTING FIRE SPRINKLER RISER.

SHEET KEYNOTES

- CONNECT TO EXISTING 6" WASTE LINE HERE.
- CONNECT TO EXISTING 10" STORM DRAIN LINE HERE.
- EXISTING SMALL CABINET FAN.
- CONNECT TO EXISTING DUCT HERE.
- DEDUCTIVE ALTERNATE: IF PIPE MATERIAL MEETS CURRENT CODE ITEMS IT DOES NEED TO BE REPLACED. (SEE IPC 2003 TABLE 702.2 FOR CODE COMPLIANT UNDERGROUND PIPE MATERIALS).
- TURN 72"x14" SUPPLY AIR DOWN WITH 45" ELBOW AND CONNECT TO 22"φ SUPPLY AIR PLENUM.
- TURN 28"x10" DUCT DOWN INTO 28"x18" ELBOW AND CONNECT INTO 18"φ SUPPLY AIR DUCT.
- TRANSITION TO 60/16 AND BLANK OFF UNUSED PORTION OF LOUVER. SEE DIVISION 11 SPECIFICATIONS.

UVSC HALLWAY ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS
DESIGN DEVELOPMENT

Revision # Date

.....

Axis Job # 0510
Owner #
Date 11/29/05
Drawn JTB
Checked TMB

MECHANICAL
FLOOR PLAN

MH101

Axis Architects

610 " I " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-6578

By: Paul Jan 18, 2006 - 3:29pm
F:\2005\316A\DRAWING-316A-EG101.dwg

D

C

B

A

FIXTURE SCHEDULE

TYPE	DESCRIPTION	CATALOG NUMBER	VOLTS	LAMPS
A	AIRCRAFT CABLE PENDANT MOUNTED LINEAR FLUORESCENT 1/2 X 1/2 ACRYLIC EGGRATE LOUVER BLACK PAINT; ELECTRONIC BALLASTS; LENGTHS AS SHOWN ON DRAWINGS; PENDANT LENGTH PER ARCHITECT	LINEAR SQ661-D-2-277-ET8-277-SPL-SXX-BLACK-FU-20	277	(2) F32 T8 835 PER 4'

DEMOLITION NOTES

- COORDINATE ALL NEW ELECTRICAL EQUIPMENT REQUIREMENTS AND MAKE CONNECTION TO EXISTING SYSTEMS. THIS INCLUDES LIGHTING, POWER, SIGNAL, RACEWAY AND OTHER SYSTEMS INCLUDED UNDER DIVISION 16.
- RELOCATE, REWIRE AND/OR RECONNECT EXISTING ELECTRICAL DEVICES AND/OR EQUIPMENT THAT FOR ANY REASON OBSTRUCTS CONSTRUCTION.
- CONCEAL ALL RACEWAY AND WIRING IN EXISTING WALLS, CEILINGS, FLOORS, ETC. EXCEPT WHERE THE USE OF SURFACE METAL RACEWAYS (E.G. WIRE MOLD) IS INDICATED ON DRAWINGS OR IN SPEC.
- LEAVE ALL EXISTING EQUIPMENT, IN PORTIONS OF THE BUILDING NOT BEING REMODELED, IN WORKING CONDITION. RESTORE ALL INTERRUPTED BRANCH CIRCUITS, FEEDERS, ETC. TO WORKING CONDITION.
- EXISTING RACEWAYS MAY BE REUSED (IN PLACE) WHERE POSSIBLE, AND WHERE IN COMPLIANCE WITH THE SPECIFICATIONS AND THE INTENT OF THE CONTRACT DOCUMENTS. INSURE INTEGRITY OF EXISTING RACEWAY BEFORE REUSE.
- REMOVE ALL RACEWAYS, CONDUCTORS, BOXES, DEVICES, EQUIPMENT, ETC. THAT ARE NOT TO BE REUSED.
- REMOVE EXISTING LIGHT FIXTURES WHICH ARE NOT TO BE REUSED, PLACE IN CARTON, LABEL APPROPRIATELY, AND RETURN TO OWNER, OR PROPERLY DISPOSE OF FIXTURES THAT THE OWNER CHOOSES NOT TO KEEP.
- DO NOT PENETRATE STRUCTURAL ELEMENTS OF FLOORS, WALLS, CEILINGS, ROOFS, ETC.
- DISCONNECT AND RECONNECT ANY/ALL FIXTURES, DEVICES, EQUIPMENT, ETC. REQUIRED FOR PROPER COMPLETION OF THE WORK.

GENERAL NOTES

- CONSULT ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATION OF ALL LIGHTING FIXTURES.
- VERIFY ALL EQUIPMENT DIMENSIONS AND LOCATIONS BEFORE BEGINNING ROUGH IN. CONSULT ALL APPLICABLE CONTRACT DRAWINGS AND SHOP DRAWINGS TO INSURE NEC CODE CLEARANCES REQUIRED AROUND ALL ELECTRICAL EQUIPMENT.
- CONTRACTOR SHALL VERIFY ALL ELECTRICAL LOADS (VOLTAGE, PHASE, CONNECTION REQUIREMENTS, ETC.) OF EQUIPMENT FURNISHED UNDER DIVISION 15 WITH APPROVED MECHANICAL SHOP DRAWINGS BEFORE BEGINNING ROUGH IN.
- SEE SECTION 16510 OF THE SPECIFICATION REQUIRED COORDINATION MEETINGS WITH MECHANICAL AND CEILING CONTRACTORS.
- SEE APPLICABLE SHOP DRAWINGS FOR ROUGH IN LOCATION OF ALL EQUIPMENT, WIRING DEVICES, ETC. WHERE APPLICABLE MOUNT ALL WIRING DEVICES ABOVE BACK SPLASH EXCEPT THOSE SERVING UNDER COUNTER EQUIPMENT.
- SEE SPECIFICATION FOR ENERGY SAVING LAMP AND BALLAST REQUIREMENTS.
- FINISHES OF ALL LIGHT FIXTURES SHALL BE AS SELECTED BY ARCHITECT.
- THE ELECTRICAL CONTRACTOR SHALL NOTIFY AND COOPERATE WITH THE MECHANICAL CONTRACTOR SUCH THAT NO PIPING, DUCTS, OR EQUIPMENT FOREIGN TO THE OPERATION OF THE ELECTRICAL EQUIPMENT SHALL BE PERMITTED TO BE INSTALLED IN, ENTER OR PASS THRU ELECTRICAL ROOMS OR SPACES, OR ABOVE OR BELOW ELECTRICAL EQUIPMENT IN OTHER AREAS.
- ELECTRICAL BOXES SHALL NOT BE LOCATED IN MASONRY COLUMNS IN BRICK WALLS OR IN GROUTED CELLS ADJACENT TO OPENINGS. COORDINATE LOCATION OF BOXES WITH MASONRY CONTRACTOR.
- ALL PENETRATIONS OF FIRE RATED FLOORS, WALLS, AND CEILINGS SHALL BE SEALED WITH APPROVED MATERIAL TO MAINTAIN FIRE RATING OF SURFACE PENETRATED.
- CIRCUITS EXTENDING OVER 70' FOR 120 VOLT AND 165' FOR 277 VOLT 20 AMP CIRCUITS SHALL BE RUN WITH MINIMUM #10 CONDUCTORS.

INDEX OF ELECTRICAL DRAWINGS

EG101 SYMBOLS, SCHEDULES AND NOTES
EE101 ELECTRICAL FLOOR PLAN

ELECTRICAL SYMBOL SCHEDULE

- SEE FIXTURE SCHEDULE FOR TYPE, MOUNTING AND WATTAGE.
- HEIGHT MEASURED TO CENTER LINE OF THE BOX FROM THE FINISH FLOOR.
- REFER TO DRAWINGS FOR DIRECTIONAL ARROWS.
- SUBSCRIPT KEYS SWITCH TO FIXTURES CONTROLLED.
- NEMA TYPE 'ND' NON-FUSED UNLESS NOTED 'F' (FUSED). USE 'HD' 480 V.
- HEIGHT TO BE THE LOWER OF EITHER 80" A.F.F. OR 6" BELOW CEILING.
- PROVIDE H.O.A. AND S.S. PUSHBUTTONS AS REQUIRED.
- DOUBLE ARROWS DENOTE A DOUBLE FACE UNIT.
- COORDINATE WITH MILLWORK SHOP DRAWINGS AND ELEVATIONS FOR HEIGHT.
- SUBSCRIPT DENOTES NEMA CONFIGURATION.
- HEIGHT MEASURED TO BOTTOM OF THE BOX FROM FINISH FLOOR.

STANDARD MOUNTING HEIGHT UNLESS OTHERWISE NOTED ON PLANS

SYMBOL	DESCRIPTION	MOUNTING HEIGHT	NOTES
	ONE CIRCUIT, TWO WIRE HOME RUN TO PANEL		
	2 CIRCUIT, 3 WIRE, COMMON NEUTRAL HOME RUN		
	3 CIRCUIT, 4 WIRE, COMMON NEUTRAL HOME RUN		
	CONDUIT UP		
	CONDUIT DOWN		
	CONDUIT STUB LOCATION	CAP CONDUIT	
	CABLE TRAY	AS NOTED	
	FLUORESCENT LIGHT FIXTURE	AS NOTED	1
	FLUORESCENT EGRESS LIGHT FIXTURE	AS NOTED	UNSWITCHED
	CEILING MOUNTED EXIT LIGHT	CEILING	1.3.8.
	SINGLE POLE SWITCH	+4'-0"	2.
	OCCUPANCY SENSOR	CEILING	
	POWER PACK	CEILING	SEE DIAGRAM, SPEC.
	DUPLEX RECEPTACLE	+16" OR AS NOTED	9. 11.
	WEATHERPROOF RECEPTACLE	+24" OR AS NOTED	2. 9.
	MULTIPLE SERVICE FLOOR BOX	FLOOR	
	DATA OUTLET	+16" OR AS NOTED	9. 11.
	PANEL BOARD	TOP AT +6'-0"	
	FIRE ALARM SIGNAL HORN/STROBE	+6'-8"	6.
	ARCHITECTURAL ROOM NUMBER		
	LIGHT FIXTURE (LETTER DESIGNATES TYPE)		



UVSC HALLWAY
ADDITION - DFCM
PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision # Date

.....

Axis Job # 0510
Owner #
Date 11-29-05
Drawn BNA
Checked EF


SYMBOLS,
SCHEDULES
AND NOTES

EG101


Axis Architects

610 " I " STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578

By: Paul, Jan 18, 2006 - 3:29pm
F:\2005\316A\DRAW\B-316A-EE101.dwg



PLAN NORTH
LIGHTING PLAN
1/8" = 1'-0"
0' 4' 8' 16'



PLAN NORTH
POWER PLAN
1/8" = 1'-0"
0' 4' 8' 16'

SHEET KEYNOTES

- 1 REMOVE EXISTING WEATHERPROOF OUTLET AND COVER PLATE AND REPLACE WITH NEW 20 AMP OUTLET AND STAINLESS STEEL COVER PLATE.
- 2 PROVIDE 1" CONDUIT BETWEEN EACH FLOOR BOX FOR DATA; RUN CONDUIT UP THE WALL AT LOCATION SHOWN AND THEN STUB TO CABLE TRAY. PROVIDE PULL STRING IN ALL RACEWAYS.
- 3 PAINT WALL MOUNTED CONDUITS TO MATCH EXISTING WALL SURFACE. PER ARCHITECT'S INSTRUCTIONS. RUN CEILING CONDUIT IN UVSC STANDARD ELECTRICAL ZONE AREA, AND PAINT CONDUIT TO MATCH EXISTING ELECTRICAL CONDUITS.
- 4 CIRCUIT TO 20 AMP 1 POLE CIRCUIT BREAKERS IN EXISTING PANEL INDICATED. PANELS ARE LOCATED IN MECHANICAL MEZZANINE ABOVE. FIELD VERIFY EXACT LOCATION. PROVIDE A SEPARATE NEUTRAL FOR EACH CIRCUIT.
- 5 ADD A NEW 75 CANDELA STROBE ON COLUMN, AND TIE TO EXISTING FIRE ALARM INDICATING LOOP STROBE SHALL BE UL LISTED TO BE USED WITH EXISTING FIRE ALARM SYSTEM. INSTALL STROBE IN SURFACE WIREMOLD BOX. WIRING SHALL BE INSTALLED IN WIREMOLD SURFACE RACEWAY. MINIMUM WIRE SIZE SHALL BE #14 AWG OF THE TYPE RECOMMENDED BY THE FIRE ALARM MANUFACTURER.



UVSC HALLWAY ADDITION - DFCM

PHYSICAL EDUCATION BLDG UVSC CAMPUS

Revision # Date
.
.
.
.

Axis Job # 0510
Owner #
Date 11-29-05
Drawn BNA
Checked EF

ELECTRICAL
FLOOR PLAN

EE101

Axis Architects

610 "I" STREET SALT LAKE CITY UTAH 84103 P 355-3003 F 355-8578