


DEMOLITION KEYNOTE LEGEND

- 1A REMOVE PARAPET CAP
- 1B REMOVE BALLAST AND ROOFING - STRIP DOWN TO EXISTING T&G WOOD DECK
- 1C REMOVE AND SALVAGE MECHANICAL EQUIPMENT FOR RE-USE
- 1D DEMO ABANDON MECHANICAL VENT STACK
- 1E REMOVE ROOF DRAIN AND DRAIN COMPONENTS COMPLETELY
- 1F REMOVE AND SALVAGE SKYLIGHT FOR RE-USE
- 1G REMOVE AND SALVAGE RADIO ANTENNA MAST - SERVICE TO ANTENNA IS NOT TO BE INTERRUPTED DURING CONSTRUCTION - CONTRACTOR TO PROVIDE SAFE TEMPORARY LOCATION FOR USE DURING CONSTRUCTION TO BE APPROVED BY OWNER PRIOR TO CONSTRUCTION
- 1H EXISTING ADJACENT ROOF TO REMAIN- CONTRACTOR TO PROTECT
- 1J BOMB BLAST ROOF - REMOVE FOR IN FILL SEE STRUCTURAL DETAIL C/SE201
- 1K ANCHOR AND GUY WIRES FOR ANTENNA MAST - REMOVE AND SALVAGE FOR OWNERS USE
- 1L REMOVE EXISTING ROOF HATCH. ENLARGE OPENING TO ACCOMMODATE SPECIFIED NEW ROOF HATCH
- 1M REMOVE EXISTING STEEL RAILING
- 1N REMOVE AND SALVAGE ANTENNA MAST CRANK - SEE NOTE "1G" ABOVE
- 1P ANCHOR TO REMAIN UNDISTURBED
- 1Q EXISTING METAL FACIA AND SCUPPER TO REMAIN
- 1R REMOVE EXISTING FLASHING AROUND MECHANICAL VENT. EXTEND VENT MIN. 8" ABOVE NEW ROOF FLASHING
- 1S REMOVE EXISTING ROOF SYSTEM DOWN TO EXISTING CONCRETE CANOPY STRUCTURE
- 1T REMOVE EXISTING MASONRY REGLET FLASHING. SALVAGE FOR RE-USE

GENERAL DEMOLITION NOTES

- CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION.
- WHERE EXISTING ROOF DEMOLITION IS INDICATED, MEASURES MUST BE TAKEN TO AVOID DAMAGING OTHER BUILDING ELEMENTS. WHERE INSULATION REMOVAL IS INDICATED, MEASURES MUST BE TAKEN TO AVOID DAMAGING WOOD DECK OR OTHER BUILDING ELEMENTS.
- ELECTRICAL CONDUIT MAY BE EXPOSED DURING DEMOLITION. CONTRACTOR TO PROTECT CONDUIT.
- DISCONNECT UTILITIES TO MECHANICAL UNITS PRIOR TO REMOVAL. SECURELY STORE FOR RE-INSTALLATION AS INDICATED. EQUIPMENT DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR.
- CONTRACTOR TO COORDINATE DEMOLITION STAGING AREAS WITH OWNER.
- CONTRACTOR TO PROVIDE AND USE WASTE CHUTE FOR DEMOLITION DEBRIS.



SE101

Structural Sheet

Axis Architects

352 South Denver St. Suite 205 Salt Lake City, Utah 84111

Utah State UNIVERSITY

State of Utah-Department of Administrative Services
DIVISION OF FACILITIES CONSTRUCTION
1410 West Center Street, Salt Lake City, Utah 84143-0001

Physical Facilities Building
Roofing Improvements

Utah State University
Construction Documents

Revision # Date

.....

Axis Job # 0612
Owner # 06021730
Date 2006.15.06
Drawn
Checked

