



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

D'ARCY DIXON PIGNANELLI
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN
Director

ADDENDUM #1

Date: 13 September 2005

To: Contractors

From: Wayne Smith, Project Manager

Reference: Utah National Guard Camp Williams
Utah Avenue Storm Drain
DFCM Project No. 03265480

Subject: **Addendum No. 1**

Pages Addendum 1 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- 1.1.1 Dwg sheet 3 change curb type from a "normal type" to a "roll type" curb from Station 10+03 to 12+43. This will also require lowering the profile approximately 2.5 inches. The intent is to match the existing asphalt on both sides of the curb as close as possible.
- 1.1.2 Dwg sheet 3 the existing catch basin at Station 10+00 has been relocated (under a separate project) to Station 10+24. The connection to this catch basin will require the adjustment of the grate to match the new gutter flowline elevation
- 1.1.3 Dwg sheet 3 remove large concrete block over ditch at Station 11+00.
- 1.1.4 Dwgs 3-5 driveway approaches to be changed to curb cuts with asphalt removal and replacement a minimum of 4 feet behind proposed curb to match existing asphalt.

End of Addendum