



Olene S. Walker
Governor
S. Camille Anthony
Executive Director
F. Keith Stepan
Director

State of Utah

Division of Facilities Construction & Management

Department of Administrative Services
4110 State Office Building
Salt Lake City, Utah 84114
Phone (801) 538-3018
Fax (801) 538-3267

MEMORANDUM

Date: 1 October 2004

To: Bidders

From: Kurt Baxter, Project Manager, DFCM

Reference: **DFCM Project # 04008400**
DHS Clearfield Office 2nd Floor Buildout

Subject: **Addendum No. 4**

4.1 The wall along the north side of the conference (202) and break (203) rooms, as well as the west side of the waiting (201) room should be called out by keyed note #2 on AE101.

Basically, the vapor retarder and batt insulation need to be repaired and reattached, and drywall should be installed at all existing walls if it was not completed during the previous phase of construction.

4.2 Regarding the project specification 06402 Interior Architectural Woodwork part 2.1 line 4 should be replaced with the following:

4. The contractor may choose any woodwork fabricator that they determine has met the qualification of the specifications.

End of Addendum