



John C. Shirley

Corey R. Solum

Christopher D. Jensen

Gregory L. Steffensen

August 30, 2004

ADDENDUM #2 for BASE BID #2

PROJECT: JLTC – Building #1 (Building + Alternates)
Camp Williams
Draper, UT 84065

BID DATE: August 31, 2004

BID TIME: 3:00 p.m.

Please note and include the following items to the contract documents. The General Contractor shall be responsible to incorporate these changes into the Contract Documents and shall also be responsible to notify all sub-contractors of this addendum.

PROJECT MANUAL:

1. SECTION 09512 Acoustical Tile Ceilings:
 - 1.1. (Delete) section 2.4.
 - 1.2. (Revise) section 2.3 to provide the following Acoustical Tile or equal:
 - 1.2.1. Manufacturer: Armstrong
 - 1.2.2. Model: Cortega 769A
 - 1.2.3. Style: Fissured, square lay-in.
 - 1.2.4. Size: 2 ft. x 4 ft.
 - 1.3 (Revise) section 2.6 to provide the following Metal Suspension System or equal:
 - 1.3.1 Manufacturer: Armstrong
 - 1.3.2 Model: Prelude XL
 - 1.3.3 Size: 15/16 inch

CONSTRUCTION DOCUMENTS:

2. (Revise): Addendum #1 BID DATE: Which reads *August 27, 2004* should be changed to read *August 31, 2004*.
3. Base Bid #1 – (Site Utilities) and Base Bid #2 – (Building + Alternates) we have tried to make this clear that these are two separate projects and require one lump sum bid to be submitted for each of these projects that the Contractor wishes to do the work for.
4. SHEET A-602 Window Schedule:
 - 4.1. (Revise) Window elevation E on A1/A-602 door dimension is 3'-0" not the 2'-11" shown. Center mullion is fixed and panic hardware is standard.
 - 4.2. Finish Schedule: (Add) In Women's Restroom #107 and Men's Restroom #105 provide PPG high-performance coating as specified; all other rooms, provide similar colors as per PF-1 & PF-2 but, paint is to be a Latex Enamel; semi-gloss; 2 coats over 1 coat of primer.
5. SHEET I-200 Interior Finish Schedules:
 - 5.1. Paint Finish Legend: (Delete) The paint finish tag *PF-3* Elevation A on A4/I-205 and Elevation E & D on A4/I-206.
 - 5.2. Finish Schedule: (Add) In Women's Restroom #107 and Men's Restroom #105 provide PPG high-performance coating as specified; all other rooms, provide similar colors as per PF-1 & PF-2 but, paint is to be a Latex Enamel; semi-gloss; 2 coats over 1 coat of primer.
 - 5.3. Finish Schedule: (Revise) When ceiling type C-1 is called out omit ceiling finish of PF-1.

End of Addendum #2