



September 7, 2004

**DFCM PROJECT # 04077750**

**PARTIAL REROOF TO:  
UNIVERSITY OF UTAH  
HUNTSMAN CENTER &  
HPER EAST & HPER NORTH**

**ADDENDUM NO. 1**

The Architect as a clarification and addition issues the data included herein to drawings, specifications, and contract documents relative to the above project. Except as effected by data herein, all other parts of the Contract Documents shall remain in full force and effect as issued by the Architect, August 24, 2004 (This Date Applies to all Project Bid Documents). It shall be the sole responsibility of the bidder to appropriately disseminate this data to all concerned prior to the assigned bid date and time. Receipt of the addendum shall be recorded by the bidder in the appropriate space on the proposal form included in the Contract Documents.

**I. GENERAL ITEMS**

**Item #1** For membrane and insulation applications mechanically fasten all metal roof decks, and fully adhere all concrete roof decks.

**II. DRAWING ITEMS**

**Item #1** Roofs #1, 3, 5 & 7 roof decks are concrete in lieu of 1-1/2" metal deck originally shown. Also provide a tapered polyiso insulation cricket at the drains – refer to Supplementary Drawings ASD-01

**Item #2** Sheet AE-101 keyed note #7, sheet AE-102 keyed note #6, sheet AE-103 keyed note #12, sheet AE-104 keyed note #10. Change all keyed notes to say:

*“NEW TAPERED EPS INSULATION CRICKET – ALL CRICKETS ARE TO SLOPE A MIN. OF ¼” PER FOOT @ VALLEYS – CRICKET INSULATION TO BE EPS SANDWICHED BETWEEN EACH LAYER OF POLYISO INSULATION – CONTRACTOR TO PROVIDE FINAL DESIGN OF CRICKETS.*

---

*“Our Success Is Measured By The Level Of Our Client's Success”.*

SCOTT P. EVANS – ARCHITECT & ASSOCIATES P.C.  
108 West Center Street, Bountiful, Utah 84010  
Phone 801-298-1368 Fax 801-298-2192 spevans@qwest.net

- Item #3** Delete detail B1/AE-501 – replace with attached supplementary drawing 01/ASD-03.
- Item #4** Delete detail A2/AE-501 & A4/AE-502 – replace with attached supplementary drawing 01/ASD-04.
- Item #5** Sheet AE-103 keyed note #9, sheet AE-104 keyed note #7 – delete keyed notes and replace with the following:
- “EXISTING WOOD CRICKET SYSTEM TO REMAIN – REMOVE A 24”X24” SECTION OF PLYWOOD EVERY 30’ AND INSPECT ALL WOOD FOR DRY-ROT – CALL THE ARCHITECT FOR A VISUAL INSPECTION – IF DRY-ROT IS FOUND A CHANGE ORDER WILL BE MADE TO REBUILD A WOOD CRICKET AND FILL ALL CAVITIES WITH BATT INSULATION.”*

### **III. SPECIFICATION ITEMS**

- Item #1** **Section 01100 Summary**  
Part 1 – General  
1.2 / D - Delete lines 2 & 3
- Item #2** **Section 07540 – Thermoplastic Membrane Roofing**  
Delete this entire section & replace with the new attached:  
Section 07540 – Thermoplastic Membrane Roofing

## **SECTION 07540 - THERMOPLASTIC MEMBRANE ROOFING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Adhered membrane roofing system.
  - 2. Mechanically fastened membrane roofing system.
  - 3. Roof insulation.
- B. Related Sections include the following:
  - 1. Division 6 Section "Rough Carpentry" for wood nailers, curbs, and blocking.
  - 2. Division 7 Section "Sheet Metal Flashing and Trim" for metal roof penetration flashings, flashings, and counterflashings.
  - 3. Division 7 Section "Joint Sealants."

#### **1.3 DEFINITIONS**

- A. Roofing Terminology: Refer to ASTM D 1079 and glossary of NRCA's "The NRCA Roofing and Waterproofing Manual" for definition of terms related to roofing work in this Section.
- B. Design Uplift Pressure: The uplift pressure, calculated according to procedures in SPRI's "Wind Load Design Guide for Fully Adhered and Mechanically Fastened Roofing Systems," before multiplication by a safety factor.
- C. Factored Design Uplift Pressure: The uplift pressure, calculated according to procedures in SPRI's "Wind Load Design Guide for Fully Adhered and Mechanically Fastened Roofing Systems," after multiplication by a safety factor.

#### **1.4 PERFORMANCE REQUIREMENTS**

- A. General: Provide installed roofing membrane and base flashings that remain watertight; do not permit the passage of water; and resist specified uplift pressures, thermally induced movement, and exposure to weather without failure.
- B. Material Compatibility: Provide roofing materials that are compatible with one another under conditions of service and application required, as demonstrated by roofing membrane manufacturer based on testing and field experience.

- C. Roofing System Design: Provide a membrane roofing system that is identical to systems that have been successfully tested by a qualified testing and inspecting agency to resist uplift pressure calculated according to ASCE 7.
  - 1. Corner Uplift Pressure: 25 lbf/sq. ft. (200 min. s.f.)
  - 2. Perimeter Uplift Pressure: 25 lbf/sq. ft. (10' min. width)
  - 3. Field-of-Roof Uplift Pressure: 22 lbf/sq. ft.
- D. FMG Listing: Provide roofing membrane, base flashings, and component materials that comply with requirements in FMG 4450 and FMG 4470 as part of a membrane roofing system and that are listed in FMG's "Approval Guide" for Class 1 or noncombustible construction, as applicable. Identify materials with FMG markings.
  - 1. Fire/Windstorm Classification: Class 1A- 90.
  - 2. Hail Resistance: MH.

#### 1.5 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other Work.
  - 1. Base flashings and membrane terminations.
  - 2. Tapered insulation, including slopes.
  - 3. Insulation fastening patterns.
  - 4. Fully adhered attachment systems.

#### 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's warranty.
- B. Installer must also be on the pre-selected list previously selected by the Owner.
- C. Manufacturer Qualifications: A qualified manufacturer that has UL listing and FMG approval for membrane roofing system identical to that used for this Project. See part 2 for other qualification requirements.
- D. Source Limitations: Obtain components for membrane roofing system from or approved by roofing membrane manufacturer.
- E. Fire-Test-Response Characteristics: Provide membrane roofing materials with the fire-test-response characteristics indicated as determined by testing identical products per test method below by UL, FMG, or another testing and inspecting agency acceptable to authorities having jurisdiction. Materials shall be identified with appropriate markings of applicable testing and inspecting agency.
  - 1. Exterior Fire-Test Exposure: Class A; ASTM E 108, for application and roof slopes indicated.
  - 2. Fire-Resistance Ratings: ASTM E 119, for fire-resistance-rated roof assemblies of which roofing system is a part.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
  - 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.
- D. Handle and store roofing materials and place equipment in a manner to avoid permanent deflection of deck.

## 1.8 PROJECT CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

## 1.9 WARRANTY

- A. Special Warranty: See attached "GUARANTEE FOR SINGLE PLY ROOFING" included in the Owner's RFP.
- B. Special Project Warranty: See attached "CONTRACTOR ROOFING WARRANTY" included in the Owner's RFP.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply for product selection:
  - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the manufacturers specified.

### 2.2 PVC ROOFING MEMBRANE

- A. PVC Sheet: ASTM D 4434, Type III, fabric reinforced.
- B. PVC Sheet: ASTM D 4434, Type III, fabric reinforced.
  - 1. Manufacturers:

- a. Manufacture must be listed in NRCA's low slope roofing materials guide.
- b. Manufacture must have a successful 10-year history.
- c. Manufacture must agree to and be willing to sign the appropriate State of Utah (DFCM) manufacturers warranty for the roofing system.
- d. Manufacturer will provide at not additional cost to Owner, progress inspections as conditions require and a final warranty inspection at project completion by a full-time technical representative.

## 2. PVC Requirements

- a. 10-year minimum performance history
- b. No documented failures in the above 10 year history
- c. Only balanced sheets will be acceptable. Scrim must be in center of membrane with no less than 20 mils polymer above scrim.
- d. Thickness: 60 mils (57 mil minimum).
- e. Exposed Face Color: White.

## 2.3 AUXILIARY MATERIALS

- A. General: Auxiliary materials recommended by roofing system manufacturer for intended use and compatible with membrane roofing.
  - 1. Liquid-type auxiliary materials shall meet VOC limits of authorities having jurisdiction.
- B. Sheet Flashing: Manufacturer's standard sheet flashing of same material, type, reinforcement, thickness, and color as PVC sheet membrane.
- C. Bonding Adhesive: Manufacturer's standard solvent-based bonding adhesive for membrane, and solvent-based bonding adhesive for base flashings.
- D. Metal Termination Bars: Manufacturer's standard predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch thick; with anchors.
- E. Metal Battens: Manufacturer's standard aluminum-zinc-alloy-coated or zinc-coated steel sheet, approximately 1 inch wide by 0.05 inch thick, prepunched.
- F. Fasteners: Factory-coated steel fasteners and metal or plastic plates meeting corrosion-resistance provisions in FMG 4470, designed for fastening membrane to substrate, and acceptable to membrane roofing system manufacturer.
- G. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, termination reglets, cover strips, and other accessories.

## 2.4 ROOF INSULATION

- A. General: Provide preformed roof insulation boards that comply with requirements and referenced standards, selected from manufacturer's standard sizes and of thicknesses indicated.
- B. Polyisocyanurate Board Insulation: ASTM C 1289, Type II, felt or glass-fiber mat facer on both major surfaces.
  - 1. Available Manufacturers:

- a. Atlas Roofing Corporation.
  - b. Carlisle SynTec Incorporated.
  - c. Celotex Corporation.
  - d. Firestone Building Products Company.
  - e. GAF Materials Corporation.
  - f. GenFlex Roofing Systems.
  - g. Johns Manville International, Inc.
  - h. RMAX.
- C. Molded-Polystyrene Board Insulation: ASTM C 578 Type VIII, 1.15-lb/cu. ft. minimum density. This is to be used to form the cricket and sloped areas of the roof and is to be installed between the two layers of polyisocyanurate insulation.
  - 1. Available Manufacturers:
    - a. Manufacturers with a third-party certification program satisfying model building code mandatory requirements for foam plastics and that produce FMG-approved molded polystyrene.
  - 2. Tapered Insulation: Provide factory-tapered insulation boards fabricated to slope of 1/4 inch per 12 inches, unless otherwise indicated.
  - 3. Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated. Material to be expanded polystyrene (EPS).

## 2.5 INSULATION ACCESSORIES

- A. General: Roof insulation accessories recommended by insulation manufacturer for intended use and compatible with membrane roofing.
- B. Fasteners: Factory-coated steel fasteners and metal or plastic plates meeting corrosion-resistance provisions in FMG 4470, designed for fastening roof insulation to substrate, and acceptable to roofing system manufacturer.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:
  - 1. Verify that roof openings and penetrations are in place and set and braced and that roof drains are securely clamped in place.
  - 2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
  - 3. Verify that surface plane flatness and fastening of steel roof deck comply with requirements in Division 5 Section "Steel Deck."
  - 4. Verify that minimum concrete drying period recommended by roofing system manufacturer has passed.
  - 5. Verify that concrete substrate is visibly dry and free of moisture. Test for capillary moisture by plastic sheet method according to ASTM D 4263.

6. Verify that concrete curing compounds that will impair adhesion of roofing components to roof deck have been removed.
7. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
- B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.
- C. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

### 3.3 INSULATION INSTALLATION

- A. Coordinate installing membrane roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.
- B. Comply with membrane roofing system manufacturer's written instructions for installing roof insulation.
- C. Install tapered insulation between layers of polyisocyanurate board to conform to slopes indicated.
- D. Install two or more layers of insulation under area of roofing to achieve required thickness. Where overall insulation thickness is 1-1/2 inches or greater, install 2 or more layers with joints of each succeeding layer staggered from joints of previous layer a minimum of 6 inches in each direction.
- E. Trim surface of insulation where necessary at roof drains so completed surface is flush and does not restrict flow of water.
- F. Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows, abutting edges and ends between boards. Fill gaps exceeding 1/4 inch with insulation.
  1. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.
- G. Mechanically Fastened Insulation: Install each layer of insulation and secure to deck using mechanical fasteners specifically designed and sized for fastening specified board-type roof insulation to deck type.
  1. Fasten insulation according to requirements in FMG's "Approval Guide" for specified Windstorm Resistance Classification.
  2. Fasten insulation to resist uplift pressure at corners, perimeter, and field of roof.
- H. Where concrete deck occurs, clean, prime and otherwise prepare the existing concrete deck as required by the used roofing system manufacturer's. Fully adhere the new insulation to the concrete deck as required by the used roofing manufacturer, to meet all uplift requirements as called out in this document.

### 3.4 ADHERED ROOFING MEMBRANE INSTALLATION



- A. Install roofing membrane over area to receive roofing according to membrane roofing system manufacturer's written instructions. Unroll roofing membrane and allow to relax before installing.
  - 1. Install sheet according to ASTM D 5036.
- B. Start installation of roofing membrane in presence of membrane roofing system manufacturer's technical personnel.
- C. Accurately align roofing membrane and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- D. Bonding Adhesive: Apply solvent-based bonding adhesive to substrate and underside of roofing membrane at rate required by manufacturer and allow to partially dry before installing roofing membrane. Do not apply bonding adhesive to splice area of roofing membrane.
- E. Bonding Adhesive: Apply water-based bonding adhesive to substrate at rate required by manufacturer and immediately install roofing membrane. Do not apply bonding adhesive to splice area of roofing membrane.
- F. Mechanically or adhesively fasten roofing membrane securely at terminations, penetrations, and perimeter of roofing.
- G. Apply roofing membrane with side laps shingled with slope of roof deck where possible.
- H. Seams: Clean seam areas, overlap roofing membrane, and hot-air weld side and end laps of roofing membrane according to manufacturer's written instructions to ensure a watertight seam installation.
  - 1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of roofing membrane.
  - 2. Verify field strength of seams a minimum of twice daily and repair seam sample areas.
  - 3. Repair tears, voids, and lapped seams in roofing membrane that does not meet requirements.
- I. Spread sealant or mastic bed over deck drain flange at deck drains and securely seal roofing membrane in place with clamping ring.
- J. Install roofing membrane and auxiliary materials to tie in to existing roofing.

### 3.5 MECHANICALLY FASTENED ROOFING MEMBRANE INSTALLATION

- A. Install roofing membrane over area to receive roofing according to roofing system manufacturer's written instructions. Unroll roofing membrane and allow to relax before installing.
  - 1. Install sheet according to ASTM D 5082.
- B. Start installation of roofing membrane in presence of roofing system manufacturer's technical personnel.
- C. Accurately align roofing membranes and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- D. Mechanically or adhesively fasten roofing membrane securely at terminations, penetrations, and perimeter of roofing.
- E. Apply roofing membrane with side laps shingled with slope of roof deck where possible.

- F. Seams: Clean seam areas, overlap roofing membrane, and hot-air weld side and end laps of roofing membrane according to manufacturer's written instructions to ensure a watertight seam installation.
  - 1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of roofing membrane.
  - 2. Verify field strength of seams a minimum of twice daily and repair seam sample areas.
  - 3. Repair tears, voids, and lapped seams in roofing membrane that does not meet requirements.
- G. Spread sealant or mastic bed over deck drain flange at deck drains and securely seal roofing membrane in place with clamping ring.
- H. In-Splice Attachment: Secure one edge of roofing membrane using fastening plates or metal battens centered within membrane splice and mechanically fasten roofing membrane to roof deck. Field-splice seam.
- I. Install roofing membrane and auxiliary materials to tie in to existing roofing.

### 3.6 BASE FLASHING INSTALLATION

- A. Install sheet flashings and preformed flashing accessories and adhere to substrates according to membrane roofing system manufacturer's written instructions.
- B. Apply solvent-based bonding adhesive to substrate and underside of sheet flashing at required rate and allow to partially dry. Do not apply bonding adhesive to seam area of flashing.
- C. Flash penetrations and field-formed inside and outside corners with sheet flashing.
- D. Clean seam areas and overlap and firmly roll sheet flashings into the adhesive. Weld side and end laps to ensure a watertight seam installation.
- E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

### 3.7 FIELD QUALITY CONTROL

- A. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion and submit report to Architect.
  - 1. Notify Architect or Owner 48 hours in advance of date and time of inspection.
- B. Repair or remove and replace components of membrane roofing system where test results or inspections indicate that they do not comply with specified requirements.
- C. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

### 3.8 PROTECTING AND CLEANING

- A. Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.

- B. Correct deficiencies in or remove membrane roofing system that does not comply with requirements, repair substrates, and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.
- C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

**END OF SECTION 07540**