



September 15, 2004

**DFCM PROJECT: 04077750**

**PARTIAL REROOF TO:  
UNIVERSITY OF UTAH  
HUNTSMAN CENTER &  
HPER EAST & HPER NORTH**

**ADDENDUM NO. 2**

The Architect as a clarification and addition issues the data included herein to drawings, specifications, and contract documents relative to the above project. Except as effected by data herein, all other parts of the Contract Documents shall remain in full force and effect as issued by the Architect, August 24, 2004 (This Date Applies to all Project Bid Documents). It shall be the sole responsibility of the bidder to appropriately disseminate this data to all concerned prior to the assigned bid date and time. Receipt of the addendum shall be recorded by the bidder in the appropriate space on the proposal form included in the Contract Documents.

**I. ARCHITECTURAL DRAWING ITEMS**

**Item #1** Delete Addendum #1 – Drawing Item #2 and replace with note to read as follows:

*“NEW TAPERED INSULATION CRICKET – ALL CRICKETS ARE TO BE DESIGNED SO ROOF WILL DRAIN WITHOUT PONDING. CONTRACTOR TO PROVIDE FINAL DESIGN OF CRICKETS. CRICKET INSULATION TO BE TAPERED EPS SANDWICHED BETWEEN EACH LAYER OF POLYISO INSULATION.” EXISTING CRICKETS WILL BE INCREASED IN SIZE AS MUCH AS CONDITIONS ALLOW. BIDDING TO NOT INCREASE SIZE OF EXISTING CRICKETS WILL NOT BE ACCEPTABLE.*

**II. MECHANICAL DRAWING ITEMS**

**Item #1** Sheet PE103:

1. Add the following text for Keyed Note 14: Existing outside air ventilator to remain. System to be temporarily removed and safely

---

*“Our Success Is Measured By The Level Of Our Client's Success”.*

SCOTT P. EVANS – ARCHITECT & ASSOCIATES P.C.  
108 West Center Street, Bountiful, Utah 84010  
Phone 801-298-1368 Fax 801-298-2192 spevans@qwest.net

stored for reinstallation. System shall be reinstalled by a qualified and licensed contractor. See outside air ventilator detail and duct through curb detail.

2. Add the following text for Keyed Note 15: Existing above roof ductwork shall be demolished as required for re-roof, see outside air ventilator detail. Provide temporary weather proof seal over exposed roof penetration.
3. Add the following text for Keyed Note 16: Provide new ductwork of same material, gauge and dimensions as ductwork demolished by this contract. Provide turning vanes in 90-degree elbow and seal connection to existing ductwork airtight.
4. Add the following text for Keyed Note 17: Existing roof drains to remain.

### **III. BID DATE**

**Item #1**

**This project will not bid on September 16, 2004 @ 3:00PM, Bid date has been postponed until September 21, 2004 @ 3:30 PM. Bids must be received prior to this time.**