Department of Corrections
Central Utah Correctional Facility – Steam and Condensate Line Replacement
DFCM Project No. 04179110
September 3, 2004

Addendum Number 3

- 1. Following contract changes are part of addendum number 3
 - Delete new manhole including water proofing. Existing manhole is to be repaired by owner. Repairs include pouring new 6 inch wall from base of manhole up to 4 foot elevation. Repairs also include new concrete floor and sump in manhole. Mechanical contractor will be required to core drill through new wall and filled openings in existing wall for new steam and condensate pipe penetrations. Core drill approximately 18 inches thick.
 - Delete repairs to domestic soft water line near manhole.
 - Utilize anchor plate detail shown for connection to boiler plant at existing manhole.
 - Electrical work as shown for new manhole shall remain in contract.
 - Steam and condensate piping inside new manhole should remain in contract. Provide new vents for existing manhole. Vents to be as shown for new manhole.
 - Delete repairs to west side of manhole.