



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

D'ARCY DIXON PIGNANELLI
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN
Director

ADDENDUM

Date: 29 September 2005

To: Contractors

From: Bill Bowen, Program Director, DFCM

Reference: State Board of Regents Conference Center
DFCM Project No. 04254300

Subject: **Addendum No. 2**

Pages	Addendum	2 page
	Attachment	0 pages
	<u>Drawings</u>	<u>0 pages</u>
	Total	6 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Reference attached addendum from MHTN Architects

**Addendum No. 2****Issued: 9/29/05**

**Addendum No. two
for the
Board of Regents Conference Center
DFCM Project No. 04254300
MHTN Project No. 2005539**

All Contractors submitting proposals on the above captioned project shall be governed by the following addendum, changes and explanations to the bidding documents and shall submit their bids in accordance therewith:

Changes to The Drawings:**A2.1 General Item**

1. Blinds called for in the specifications are to be supplied for all exterior windows as well as the storefront entry into the conference room.
2. A 4'x10' marker board shall be supplied and installed in the conference room as per specifications.
3. All stone base shall be removed and reinstalled to allow for new fire rated gyp. bd. applications where occurs. Any base damaged during removal or installation shall be replaced by the contractor. New stone base to match existing shall be installed on new walls adjacent to old with rooms where stone base occurs.
4. Concerning the protected barrier for egress through the construction zone. DFCM will accept the following: a 4' high barrier or visqueen barrier adequate to keep none construction personal from straying into construction areas. If work is to occur over head of this path the path needs to have a solid lid or work of this kind needs to be done during off work hours.

End of Addendum No. 2