

Addenda No. 1

Redwood Road Campus Parking Lot H-2

Salt Lake Community College

DFCM Project No. 05057660

May 13, 2005

No.	Description
1	The new concrete sidewalk for bid item No.13 "Furnish and Install Concrete Sidewalk at Parking Lot with Base" shall include approximately (93) ninety three - $\frac{3}{4}$ " smooth dowels drilled into the existing concrete at the Tennis Courts at 18" O.C. placed 3" from the top of sidewalk. The price for the drilling, dowels, labor, etc. shall be included in the costs for bid item No. 13.
2	The Contractor shall include the cost to furnish and install 7 new metal posts and concrete bases for 7 signs provided by the college and installed in the locations as directed by the college. Such costs shall be included in bid item No. 23 "Furnish and Install Paint Striping and Signing"
3	The Contractor shall include the costs associated with transplanting 3 of the 5 of the largest existing trees which have been identified for removal as part of bid item No. 8 "Remove and Dispose of Existing Trees and Roots and Replace with Compacted Select Fill."
4	The Contractor shall include the costs to lower approximately 175 L.F. of both 4" and 6" Irrigation line through the project. Such costs shall be included in Bid Item No. 6 "Adjust Utilities"
5	The Contractor shall include the costs to Furnish and Install approximately 220 L.F. of new coaxial cable and 220 L.F. of telephone line and 275 L.F. of new THHN 110Volt Power line to the relocated Weather Station. Such costs shall include the costs of lowering and extending (Furnishing additional) existing conduit (as required) and in re-pulling the (3) three new lines to the relocated weather station from the nearest pull box. No Splices shall be allowed. All of these costs shall be included in Bid Item No. 5 "Remove and Relocate Weather Station, Fence, New Concrete Base, Connections, Complete."
6	The Contractor shall protect, and, if-needed, lower the pump house power feed that is located under the proposed parking lot. Such power feed shall not be cut to the pump house without first giving notice to the college and shall not continue for more than 24 hours. Any costs associated with lowering the conduit and power line to the pump house shall be included in Bid Item No. 6 "Adjust Utilities."
7	The Contractor shall include a cost for the relocation, or lowering of all utilities located under the proposed parking and entrance areas and such costs shall be included in the Bid Item No. 6 "Adjust Utilities."