



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

D'ARCY DIXON PIGNANELLI
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN
Director

MEMORANDUM

Date: 9 August 2005

To: Consultants

From: Vic Middleton, DFCM

Reference: Utah Department of Corrections - Draper Prison
Wasatch Diagnostic Building and Timpanogos Dental Building HVAC
DFCM Project No. 05212100

Subject: Addendum No. 1

Pages	Addendum	1 page
	Total	1 page

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in this Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

- 1.1 RTU-1 Increase the airflow to 800 cfm
- 1.2 RTU-2 Change to 3-ton unit with a minimum of 1200 cfm. This will be a 208volt 3phase unit which will require a 3pole 30amp breaker in panel "MD". The conduit and wire size will not change.
- 1.3 RTU-3 Increase the airflow to 1200 cfm
- 1.4 RTU-4 Increase the airflow to 1800-1950 cfm
- 1.5 Panel "MD" is to fed from the existing Square D panel located outside of Infirmary building on the southeast corner. This panel is approximately 230' from the new panel "MD"(contractor to verify length). This conduit will be run along the roof to the location of panel "MD". The contractor shall provide and install a new Square D #FA36100 3ph. 100amp breaker including mounting hardware in the existing panel.
- 1.6 Gas supply from abandoned line on southwest side of roof.
- 1.7 Existing Antenna coming through curb will be removed by Corrections staff.

End of Addendum

Utah!
Where ideas connect