

ADDENDUM NO. 2

Date: February 12, 2004

PROJECT:

**Snow College
Fern Young Hall Re-Roof
150 East Center Street
Ephraim Utah 84627**

ARCHITECT:

**P+A ARCHITECTS
821 EAST KENSINGTON AVENUE
SALT LAKE CITY, UT 84105
P: 801.484.1161
F: 801.485.4640
E: parchitects@comcast.net**

The original Contract Documents issued for the above noted project are amended as noted in this Addendum. It shall be the sole responsibility of the bidder to appropriately disseminate this information to all concerned prior to the assigned bid time and date, and to coordinate the Addendum with the Contract Documents.

This Addendum consists of a total of zero (0) 8 ½"x11" AD- drawings.

If there are still unresolved questions after examining this addendum, please submit those questions via telephone or facsimile as soon as possible so that an addendum can be issued to clarify those issues in a timely manner.

General:

1. None

Drawings:

1. See architectural drawing **A-FP101**. General Note number 2 shall be changed to read as follows; "General contractor shall saw cut existing light weight concrete deck as required to install new primary and secondary roof drains. General contractor shall attach a sheet of 16 ga. galvanized sheet metal to the top of the existing light weight concrete deck to fill any voids between new roof drains and saw cut area of existing concrete deck."
2. See architectural drawing **A-DT501**. See detail 01/DT501. See note that reads "surface mounted counter flashing beyond". Surface mounted counter flashing shall not be used. General contractor shall saw cut existing stone veneer and install a cast in place riglet. General contractor shall provide a snap-in type counter flashing at cast in place riglet location.
3. General contractor will need to remove a small portion of the existing metal lath and plaster ceiling system for the installation of the new secondary roof drain line locations. After area of metal lath and plaster has been removed, secondary roof drain lines shall be located as close to the bottom cord of the existing roof truss system as possible. Removed portion of lath and plaster ceiling system will be replaced by others.

Specifications:

1. None

Civil Addendum Items:

1. None,

Structural Addendum Items:

1. None.

Mechanical Addendum Items:

1. None.

Electrical Addendum Items:

1. None.

Landscape Addendum Items:

1. None.

End of Addendum 2