



Olene S. Walker
Governor
S. Camille Anthony
Executive Director
F. Keith Stepan
Director

State of Utah

Division of Facilities Construction & Management

Department of Administrative Services
4110 State Office Building
Salt Lake City, Utah 84114
Phone (801) 538-3018
Fax (801) 538-3267

MEMORANDUM

Date: 24 January 2005

To: Bidders

From: Kurt Baxter, Project Manager, DFCM

Reference: **DFCM Project # 04206500**
DNR Water Supply Replacement

Subject: **Addendum No. 3**

See Engineers Addendum #3

End of Addendum

ADDENDUM #3

Project Name: DNR Administration Building
Water Supply Network Replacement

Project Designation:

From: WHW ENGINEERING INC.
1354 East 3300 South Suite 200
Salt Lake City, Utah
801.466.4021
801.466.8536 Fax

| To: | Attn: | Fax: |
|------------------------|-----------------|--------------|
| US MECHANICAL | BRAD BYLUND | 801.785.6025 |
| RALPH TYE & SONS | DOUG TYE | 801.262.1391 |
| HARDING MECHANICAL | AMANDA CROSBY | 801.486.5217 |
| VO BROTHERS MECHANICAL | CHET VAN ORDERN | 801.392.6461 |

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated January 12, 2005 and Addendum Number N/A dated N/A, as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of ____ page(s) and the attached drawing(s), Sheet(s) _____.

I - CHANGES TO PRIOR ADDENDA: N/A

Item I-1.

Item I-2.

II - CHANGES TO BIDDING REQUIREMENTS: N/A

Item II-1.

Item II-2.

III - CHANGES TO AGREEMENT & OTHER CONTRACT FORMS: N/A

Item III-1.

Item III-2.

IV - CHANGES TO CONDITIONS OF THE CONTRACT: N/A

Item IV-1.

Item IV-2.

V - CHANGES TO SPECIFICATIONS:

Item V-1. WHW re-issued new specifications for revision 1. New divisions. Division 9 - Sections 09250, 09900, and 09923 were added.

Item V-2.

VI - CHANGES TO DRAWINGS:

Item VI-1. WHW re-issued the drawings with revision 1 shown.

Item VI-2. Sheets PE-101 and PE-102 all piping in stairwells shall be inside a 2 hour

Item VI-3. All penetrations through fire rated walls shall match IBC requirements.

Item VI-4. Delete all DF-2's shown on PE-101, 102 and 103 and connect new piping to the existing drinking fountains from the backside sheet rock walls. Remove and replace sheet rock and paint as required. 7 (Seven) locations. No new drinking fountains are required.

Item VI-5. In mechanical room the existing piping serving the kitchen and break room is copper. Leave existing copper piping. Replace insulation only.

END of ADDENDUM